

DRAWING INDEX

| | |
|------|--|
| S0.1 | DRAWING INDEX AND LIST OF ABBREVIATIONS |
| S0.2 | GENERAL STRUCTURAL NOTES AND SPECIAL INSPECTIONS AND TESTING |
| S2.0 | MARQUEE FRAMING PLAN |
| S6.1 | STRUCTURAL DETAILS |


ABBREVIATIONS

| | | | | | |
|-------------|---|--------|--|----------|--|
| A.B. | ANCHOR BOLT | FIN. | FINISH | PART. | PARTITION |
| ACI | AMERICAN CONCRETE INSTITUTE | FLR. | FLOOR | P/C | PRECAST |
| ADD'L. | ADDITIONAL | FT. | FOOT | PCF | POUNDS PER CUBIC FOOT |
| AESS | ARCHITECTURAL EXPOSED STRUCTURAL STEEL | FTG. | FOOTING | PL | PLATE |
| AISC | AMERICAN INSTITUTE OF STEEL CONSTRUCTION INCORPORATED | GA. | GAUGE | P.P. | PARTIAL PENETRATION |
| | | GALV. | GALVANIZED | PSI | POUNDS PER SQUARE INCH |
| | | GL | GLULAM | P/T | POST-TENSIONED |
| ALT. | ALTERNATE | HORIZ. | HORIZONTAL | P.T. | PRESSURE TREATED |
| ALUM. | ALUMINUM | HSS | HOLLOW STRUCTURAL SECTION | PVC | POLYVINYL CHLORIDE |
| APA | AMERICAN PLYWOOD ASSOCIATION | IBC | INTERNATIONAL BUILDING CODE | R. RAD. | RADIUS |
| ARCH. | ARCHITECT | ICBO | INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS | RCSC | RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS |
| ASCE | AMERICAN SOCIETY OF CIVIL ENGINEERS | ICC | INTERNATIONAL CODE COUNCIL | REF. | REFERENCE |
| ASTM | AMERICAN SOCIETY FOR TESTING AND MATERIALS | ID. | INSIDE DIAMETER | RET. | RETURN |
| AWS | AMERICAN WELDING SOCIETY | IN. | INCH | REINF. | REINFORCING |
| BLDG. | BUILDING | INT. | INTERIOR | REQ'D. | REQUIRED |
| BOT. | BOTTOM | | | REQ'MTS. | REQUIREMENTS |
| BRBF | BUCKLING RESTRAINED BRACED FRAME | K | KIPS | SCHED. | SCHEDULE |
| C.G. | CENTER OF GRAVITY | KSF | KIPS PER SQUARE FOOT | S.C. | SLIP CRITICAL |
| C.I.P. | CAST IN PLACE | KSI | KIPS PER SQUARE INCH | SIM | SIMILAR |
| C.J. | CONTROL JOINT | LBS. | POUND | SLRS | SEISMIC LOAD RESISTING SYSTEM |
| C.J.P. | COMPLETE JOINT PENETRATION | L.L. | LIVE LOAD | S.O.G. | SLAB ON GRADE |
| CL | CENTERLINE | LLH | LONG LEG HORIZONTAL | SPEC. | SPECIFICATION |
| CLR. | CLEAR | LLV | LONG LEG VERTICAL | SQ. | SQUARE |
| CMU | CONCRETE MASONRY UNIT | LOC. | LOCATION | SS | STAINLESS STEEL |
| COL. | COLUMN | LONG. | LONGITUDINAL | SSMA | STEEL STUD MANUFACTURERS ASSOCIATION |
| CONC. | CONCRETE | LVF | LOW VELOCITY FASTENER | STD. | STANDARD |
| CONN. | CONNECTION | MAX. | MAXIMUM | STRUCT. | STRUCTURAL |
| CONST. | CONSTRUCTION | MBMA | METAL BUILDING MANUFACTURERS ASSOCIATION | SYM. | SYMMETRICAL |
| CONT. | CONTINUOUS | MECH. | MECHANICAL | THRU | THROUGH |
| db | BAR DIAMETER | MFR. | MANUFACTURER | T&G | TONGUE AND GROOVE |
| DBA | DEFORMED BAR ANCHOR | MIN. | MINIMUM | TJ | TRUSS JOIST |
| DET. | DETAIL | MISC. | MISCELLANEOUS | TRANS. | TRANSVERSE |
| DIA., Ø | DIAMETER | MPH | MILES PER HOUR | TS | LIGHT GAUGE TUBE STEEL |
| DIAG. | DIAGONAL | MT | MAGNETIC PARTICLE TESTING | TYP. | TYPICAL |
| D.L. | DEAD LOAD | (N) | NEW | U.N.O. | UNLESS NOTED OTHERWISE |
| DWG. | DRAWING | N.I.C. | NOT IN CONTRACT | UT | ULTRASONIC TESTING |
| ELEC. | ELECTRICAL | NOM. | NOMINAL | VERT. | VERTICAL |
| EL. | ELEVATION | NO. | NUMBER | V.I.F. | VERIFY IN FIELD |
| EQ. | EQUAL | N.T.S. | NOT TO SCALE | w/ | WITH |
| EXIST., (E) | EXISTING | o.c. | ON CENTER | WF | WIDE FLANGE |
| EXP. | EXPANSION | O.D. | OUTSIDE DIAMETER | w/o | WITHOUT |
| EXT. | EXTERIOR | OPP. | OPPOSITE | W.P. | WORK POINT |
| FDN. | FOUNDATION | OWJ | OPEN WEB JOIST | WPS | WELDING PROCEDURE SPECIFICATION |
| | | PAF | POWDER ACTUATED FASTENER | WWF | WELDED WIRE FABRIC |

File: G:\A\2019\2024\02_Egyptian Theatre\20240201.dwg TAB:Layout1
Plotted: 4/21/14 at 11:44am By: thong
XREFs: x202402B



| | |
|-------------|------------|
| PROJECT NO. | 212024.02 |
| DRAWN: | BJS |
| CHECKED: | TCS |
| DATE: | 04-15-2014 |



| |
|---|
| BID SET |
| DRAWING INDEX AND LIST OF ABBREVIATIONS |
| S0.1 |

GENERAL STRUCTURAL NOTES

THESE GENERAL NOTES SUPPLEMENT THE PROJECT SPECIFICATIONS. REFER TO THE PROJECT SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS. NOTES AND DETAILS ON THE STRUCTURAL DRAWINGS SHALL TAKE PRECEDENCE OVER THE GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE GIVEN, CONSTRUCTION SHALL BE AS SHOWN FOR SIMILAR WORK.

TEMPORARY CONDITIONS:
THE STRUCTURE IS DESIGNED TO FUNCTION AS A UNIT UPON COMPLETION. THE CONTRACTOR IS RESPONSIBLE FOR FURNISHING ALL TEMPORARY BRACING AND/OR SUPPORT THAT MAY BE REQUIRED AS THE RESULT OF THE CONTRACTOR'S CONSTRUCTION METHODS AND/OR SEQUENCES.

CONTRACTOR'S CONSTRUCTION AND/OR ERECTION SEQUENCES SHALL RECOGNIZE AND CONSIDER THE EFFECTS OF THERMAL MOVEMENTS OF STRUCTURAL ELEMENTS DURING THE CONSTRUCTION PERIOD.

EXISTING CONDITIONS:
ALL EXISTING CONDITIONS, DIMENSIONS AND ELEVATIONS SHALL BE FIELD VERIFIED. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY SIGNIFICANT DISCREPANCIES FROM CONDITIONS SHOWN ON THE DRAWINGS.

ASSUMED FUTURE CONSTRUCTION:

CODE REQUIREMENTS:

DESIGN CRITERIA:
DESIGN WAS BASED ON THE STRENGTH AND DEFLECTION CRITERIA OF THE OSSC, IN ADDITION TO THE DEAD LOADS. THE FOLLOWING LOADS AND ALLOWABLES WERE USED FOR DESIGN, WITH LIVE LOADS (LL.) REDUCED PER OSSC:

| DESIGN CRITERIA | | |
|--------------------------------------|--|-------------------|
| GRAVITY SYSTEM CRITERIA | | |
| ROOF LIVE/SNOW LOAD | 25 PSF L.L. (ALSO SEE SNOW LOAD CRITERIA BELOW) | |
| FLOOR LIVE LOADS: | UNIFORM LOAD | CONCENTRATED LOAD |
| CORRIDORS AND STAIRS | 100 PSF L.L. | 2,000 LBS. |
| ASSEMBLY AREAS, RETAIL | 100 PSF L.L. | 2,000 LBS. |
| VERTICAL FLOOR DEFLECTION (INTERIOR) | L/360 LIVE LOAD PER OSSC TABLE 1604.3 | |
| NOTES: | 1. LIVE LOADS REDUCED PER OSSC. 2. MEMBER DESIGNED FOR MORE CRITICAL OF UNIFORM OR CONCENTRATED LOAD. | |
| SNOW CRITERIA | | |
| DESIGN ROOF SNOW LOAD | 25 PSF MINIMUM IN ACCORDANCE WITH OSSC | |
| SNOW DRIFT | PER OSSC | |
| GROUND SNOW LOAD | Pg= 10 PSF IN ACCORDANCE WITH 2007 SNOW LOAD ANALYSIS FOR OREGON | |
| FLAT ROOF SNOW LOAD | Pf = 14 PSF | |
| SNOW EXPOSURE FACTOR | Ce = 1.0 | |
| SNOW LOAD IMPORTANCE FACTOR | I = 1.1 | |
| THERMAL FACTOR | Ct = 1.0 | |
| GEOTECHNICAL CRITERIA | | |
| DESIGN BASED ON REPORT BY: | NOT APPLICABLE | |
| WIND CRITERIA | | |
| MAIN WIND FORCE RESISTING SYSTEM | 100 MPH BASIC WIND SPEED (3-SECOND GUST) | |
| COMPONENTS AND CLADDINGS | 100 MPH BASIC WIND SPEED (3-SECOND GUST) | |
| EXPOSURE CATEGORY | C | |
| IMPORTANCE FACTOR | Iw = 1.15 | |
| GUST/INTERNAL PRESSURE | GC/pi = +/- 0.18 | |
| SEISMIC CRITERIA | | |
| OCCUPANCY CATEGORY | III | |
| SITE CLASS | E (ASSUMED) | |
| SEISMIC DESIGN CATEGORY | D | |
| MCB SPECTRAL ACCELERATION | Si = 1.5g | Si = 0.714g |
| SITE COEFFICIENT | Fa = 0.9 | Fv = 2.4 |
| DESIGN SPECTRAL ACCELERATION | So = 0.90g | So1 = 1.143g |

STRUCTURAL OBSERVATION:
THE STRUCTURAL ENGINEER OF RECORD (SER) WILL PERFORM STRUCTURAL OBSERVATION BASED ON THE REQUIREMENTS OF THE OSSC AT THE STAGES OF CONSTRUCTION LISTED BELOW. CONTRACTOR SHALL PROVIDE SUFFICIENT NOTICE AND ACCESS FOR THE SER TO PERFORM THESE OBSERVATIONS.

| STRUCTURAL OBSERVATIONS | | |
|--|-----------------|------------------|
| ITEM | OBSERVED BY (2) | COMMENTS |
| | SER | |
| DURING INITIAL STEEL ERECTION | X | REF. NOTES 1,3,4 |
| AS REQUIRED TO ADDRESS STRUCTURAL ISSUES | X | REF. NOTES 1,3,4 |

FOOTNOTES:

2. SER - STRUCTURAL ENGINEER OF RECORD.
3. A FIELD REPORT WILL BE SUBMITTED TO THE BUILDING DEPARTMENT FOLLOWING EACH SITE VISIT.
4. STRUCTURAL OBSERVATION IS FOR THE GENERAL CONFORMANCE OF THE STRUCTURAL DRAWING, SPECIAL INSPECTION IS STILL REQUIRED.
5. AFTER REINFORCING STEEL HAS BEEN INSTALLED.
6. CONTRACTOR SHALL COORDINATE A SITE VISIT WITH STRUCTURAL ENGINEER OF RECORD TO REVIEW AS BUILT CONDITIONS AND CONFIRM MEMBER SIZES AND CONFIGURATION FOR EXISTING ELEMENTS PRIOR TO PROCEEDING WITH ANY NEW WORK.

SUBMITTALS:
SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER PRIOR TO FABRICATION AND CONSTRUCTION OF ALL STRUCTURAL ITEMS, INCLUDING THE FOLLOWING:

| SUBMITTALS | | | |
|--------------------------|--------------------|--------------------------------|----------|
| ITEM | SUBMITTAL (1.4) | DEFERRED SUBMITTAL (2.4) | COMMENTS |
| STRUCTURAL STEEL | X | | |
| STEEL WELDING PROCEDURES | X | | |

FOOTNOTES:

2. DESIGN DRAWINGS, SHOP DRAWINGS, AND CALCULATIONS FOR THE DESIGN AND FABRICATION OF ITEMS THAT ARE DESIGNED BY OTHERS SHALL BEAR THE SEAL AND SIGNATURE OF A STRUCTURAL ENGINEER REGISTERED IN THE STATE OF OREGON AND SHALL BE SUBMITTED TO THE ENGINEER PRIOR TO FABRICATION. CALCULATIONS SHALL BE INCLUDED FOR ALL CONNECTIONS TO THE STRUCTURE CONSIDERING LOCALIZED EFFECTS ON STRUCTURAL ELEMENTS INDUCED BY THE CONNECTION LOADS. DESIGN SHALL BE BASED ON THE REQUIREMENTS OF THE OSGC AND AS NOTED UNDER 'DESIGN CRITERIA'.
3. THE CONTRACTOR SHALL COORDINATE SEISMIC RESTRAINTS OF MECHANICAL, PLUMBING, AND ELECTRICAL EQUIPMENT, MACHINERY, AND ASSOCIATED PIPING WITH THE STRUCTURE. CONNECTIONS TO STRUCTURE SHALL CONFORM TO ASCE 7-05 CHAPTER 13. BE DESIGNED BY AN ENGINEER REGISTERED IN THE STATE OF OREGON, AND SHALL BE SUBMITTED TO THE ENGINEER PRIOR TO FABRICATION.
4. FIELD ENGINEERED DETAILS DEVELOPED BY THE CONTRACTOR THAT DIFFER FROM OR ADD TO THE STRUCTURE DRAWINGS SHALL BEAR THE SEAL AND SIGNATURE OF A STRUCTURAL ENGINEER REGISTERED IN THE STATE OF OREGON AND SHALL BE SUBMITTED TO THE ENGINEER PRIOR TO CONSTRUCTION.

CONCRETE ACCESSORIES:

ALL ANCHORS SHALL BE INSTALLED IN STRICT CONFORMANCE WITH MANUFACTURER'S RECOMMENDATIONS. DO NOT CUT REINFORCING IN NEW OR EXISTING CONCRETE DURING INSTALLATION. ANCHORS EXPOSED TO EARTH OR WEATHER SHALL BE PROTECTED FROM CORROSION BY HOT-DIP GALVANIZING OR USE OF STAINLESS STEEL.

PERMANENTLY EXPOSED EMBEDDED PLATES AND ANGLES SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION, UNLESS OTHERWISE NOTED. NO LOADS OR WELDS SHALL BE PLACED ON EMBEDDED PLATES OR ANGLES FOR A MINIMUM OF 7 DAYS AFTER CASTING.

STRUCTURAL STEEL:

| STRUCTURAL STEEL | |
|-------------------------------|--|
| ASTM A36 | CHANNELS, PLATES AND ANGLES, EXCEPT AS NOTED |
| ASTM A500, GRADE B (FY=46KSI) | HOLLOW STRUCTURAL SECTIONS (TUBES) |

DESIGN, FABRICATION, AND ERECTION SHALL BE IN ACCORDANCE WITH THE "AISC SPECIFICATION FOR THE DESIGN, FABRICATION, AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS" WITH "COMMENTARY" AND THE "CODE OF STANDARD PRACTICE", WITH EXCEPTIONS NOTED IN SPECIFICATIONS.

BOLTS SHALL CONFORM TO THE ASTM AND RCSC SPECIFICATIONS FOR JOINTS USING A325 OR A490 HIGH STRENGTH BOLTS. BOLTS SHALL BE SNUG-TIGHT UNLESS NOTED OTHERWISE.

WELDING SHALL CONFORM TO THE AWS CODES FOR ARC AND GAS WELDING IN BUILDING CONSTRUCTION. WELDING SHALL BE PERFORMED IN ACCORDANCE WITH A WELDED PROCEDURE SPECIFICATION (WPS) AS REQUIRED IN AWS D1.1 AND APPROVED BY THE STRUCTURAL ENGINEER. THE WPS VARIABLES SHALL BE WITHIN THE PARAMETERS ESTABLISHED BY THE FILLER-METAL MANUFACTURER.

WELDS SHALL BE MADE USING E70XX ELECTRODES AND SHALL BE 3/16" MINIMUM, UNLESS OTHERWISE NOTED.

PROVIDE WEEP HOLES AT EXTERIOR CLOSED SECTIONS WHERE MOISTURE MAY ACCUMULATE. HOT DIP GALVANIZE ALL EXTERIOR STRUCTURAL STEEL.

LIGHT GAUGE METAL STUDS:

SPECIAL INSPECTIONS AND TESTING PROGRAM

| TABLE 1 - REQUIRED STRUCTURAL SPECIAL INSPECTIONS | | | | | | |
|---|-------------------------------|--|----------------------------|--------------------|----------|---|
| SYSTEM OR MATERIAL | | INSPECTION | | | REMARKS | |
| | | IBC CODE REFERENCE | CODE OR STANDARD REFERENCE | FREQUENCY (NOTE 5) | | |
| | | | | CONTINUOUS | PERIODIC | |
| FABRICATORS | | | | | | |
| FABRICATORS | 1704.2 | | | X | | WHERE FABRICATION OF STRUCTURAL LOAD-BEARING MEMBERS AND ASSEMBLIES IS BEING PERFORMED ON THE PREMISES OF A FABRICATOR'S SHOP, SPECIAL INSPECTION OF THE FABRICATED ITEMS SHALL BE REQUIRED BY TABLE 2 AND AS REQUIRED ELSEWHERE IN THE SPECIAL INSPECTION PROGRAM. REFERENCE SECTION 1704.2.2 FOR APPROVED FABRICATOR EXCEPTION. |
| STEEL | | | | | | |
| FABRICATION OF STRUCTURAL ELEMENTS | 1704.2 | | | | X | REFER TO INSPECTION OF FABRICATOR REQUIREMENTS |
| MATERIAL VERIFICATION OF STRUCTURAL STEEL | 1704.3 2203.1 | ASTM A6 AISC 360 A3.1 AISC 360 M5, 5 | | | X | CERTIFIED MILL TEST REPORTS |
| MATERIAL VERIFICATION OF HIGH STRENGTH BOLTS, NUTS, AND WASHERS | 1704.3.3 | AISC 360 A3.3 | | | X | MANUFACTURER'S CERTIFIED TEST REPORTS |
| MATERIAL VERIFICATION OF ANCHOR BOLTS AND THREADED RODS | 1704.3 | AISC 360 A3.4 | | | X | MANUFACTURER'S CERTIFIED TEST REPORTS |
| MATERIAL VERIFICATION OF WELD FILLER METALS | 1704.3.1 | AISC 360 A3.5 | | | X | MANUFACTURER'S CERTIFIED TEST REPORTS |
| VERIFYING USE OF PROPER WPS'S | | | | | X | COPY OF WELDING PROCEDURE SPECIFICATIONS |
| VERIFYING WELDER QUALIFICATIONS | | | | | X | COPY OF QUALIFICATION CARDS |
| COMPLETE AND PARTIAL JOINT PENETRATION GROOVE WELDS | 1704.3.1 1704.4 | AWS D1.1 SECTION 6 | | X | | ALL WELDS VISUALLY INSPECTED PER AWS D1.1.6.9 |
| MULTIPASS FILLET WELDS | | | | X | | |
| SINGLE PASS FILLET WELDS LESS THAN OR EQUAL TO 5/16" | | | | | X | |
| SNUG-TIGHT HIGH STRENGTH BOLT INSTALLATION | 1704.3 | RCSC SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS SECTION 9 AISC 360 M2.5 | | | X | ALL CONNECTIONS VISUALLY INSPECTED |
| VERIFICATION OF FRAME JOINT DETAILS INCLUDING MEMBER AND COMPONENT LOCATIONS, BRACING, AND STIFFENERS | 1704.3.2 | | | | X | |
| MATERIAL VERIFICATION OF WELD FILLER METALS | | | | | X | MANUFACTURER'S CERTIFIED TEST REPORTS |
| VERIFYING USE OF PROPER WPS'S | | | | | X | COPY OF WELDING PROCEDURE SPECIFICATIONS |
| VERIFYING WELDER QUALIFICATIONS | | | | | X | COPY OF QUALIFICATION CARDS |
| POST INSTALLED CONCRETE ANCHORS | | | | | | |
| EXPANSION ANCHORS INSTALLATION IN HARDENED CONCRETE AND COMPLETED MASONRY | 1703.4.2 1704.15 1912.1 | ICC EVALUATION REPORT ACI 318: 3.8.6, 21.1.8 | | X | X | INSPECTION REQUIREMENTS PER ICC EVALUATION REPORT |
| EPOXY ANCHORS INSTALLATION IN HARDENED CONCRETE AND COMPLETED MASONRY | | | | X | | INSPECTION REQUIREMENTS PER ICC EVALUATION REPORT |

TESTING

| TABLE 2 - REQUIRED TESTING FOR SPECIAL INSPECTIONS | | | | |
|---|--------------------|---|--------------|-------------------------------------|
| SYSTEM OR MATERIAL | TESTING | | | REMARKS |
| | IBC CODE REFERENCE | CODE OR STANDARD REFERENCE | FREQUENCY | |
| | | | CONTINUOUS | |
| MAGNETIC PARTICLE (MT) AND ULTRASONIC (UT) TESTING OF WELDS | | MT - AWS D1.1 6.14.4 UT - AWS D1.1 6.13 & 6.14.3 | PER DRAWINGS | ALL C.J.P. WELDS REQUIRE UT TESTING |

STATEMENT OF SPECIAL INSPECTION NOTES:



PERIODIC INSPECTION: THE PART-TIME OR INTERMITTENT OBSERVATION OF WORK REQUIRING SPECIAL INSPECTION BY AN APPROVED SPECIAL INSPECTOR WHO IS PRESENT IN THE AREA WHERE THE WORK HAS BEEN OR IS BEING PERFORMED AND AT THE COMPLETION OF THE WORK.

6. WHERE PERIODIC INSPECTION IS ALLOWED IN ACCORDANCE WITH AN EXPANSION ANCHOR'S ICC EVALUATION REPORT, INSPECTIONS SHALL BE AS FOLLOWS:


FOR ALL ANCHORS, PRIOR TO CONCEALMENT, VERIFY: ANCHOR TYPE, ANCHOR DIMENSIONS, ANCHOR SPACING AND EDGE DISTANCES.

- FOR EACH ANCHOR TYPE AND SIZE, INSPECTOR SHALL BE ON SITE CONTINUOUSLY INSPECT A MINIMUM OF THE FIRST 10 ANCHORS INSTALLED BY EACH INSTALLER FOR CONFORMANCE WITH ICC EVALUATION REPORT. PROVIDED ALL ANCHORS ARE INSTALLED CORRECTLY PER MANUFACTURER'S INSTRUCTIONS PROVIDE PERIODIC INSPECTION ON A MINIMUM OF 10% OF THE NEXT 1000 ANCHORS INSTALLED BY EACH INSTALLER. CONTINUOUSLY TRAINING ANCHORS BY EACH INSTALLER. INSPECTIONS SHALL OCCUR A MINIMUM OF ONCE PER WEEK AT RANDOM TIME WHILE ANCHOR INSTALLATION IS ONGOING. ANY NON-COMPLIANCE ISSUES SHALL RESET THE INSPECTION REQUIREMENTS TO TEN (10) CONTINUOUSLY TRAINING ANCHORS BY EACH INSTALLER. THE ATTENTION OF THE ENGINEER OF RECORD FOR REVIEW AND SHALL BE BROUGHT INTO COMPLIANCE BY EITHER TESTING OR RE-INSTALLATION.

- INSPECTION REPORTS SHALL IDENTIFY NAMES OF INSTALLERS






File: G:\A\2012\2024\02_Egyptian Theatre\202402520.dwg Title: Layout1
Plotted: 4/21/14 at 11:44am By: btrng
XREFs: x212024021B






- PLAN NOTES:**
- (E) INDICATES EXISTING.
 - (N) INDICATES NEW.
 - INDICATES EXISTING STRUCTURE.
 - INDICATES SPLICE LOCATION. REF. 7/S6.1 FOR DETAIL.
 - CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS, DIMENSIONS, AND ELEVATIONS PRIOR TO FABRICATION AND ERECTION AND NOTIFY ENGINEER OF ANY SIGNIFICANT DISCREPANCIES FROM THAT SHOWN ON THE DRAWINGS.
 - INDICATES EXISTING CONCRETE WALL.
 - REF. ARCH. FOR DIMENSIONS NOT SHOWN.

1 MARQUEE FRAMING PLAN
3/16"=1'-0"





| | |
|--|------------|
| CITY OF COOS BAY | |
| EGYPTIAN THEATRE PHASE 1 IMPROVEMENTS 229 SOUTH BROADWAY COOS BAY, OREGON | |
|  111 SW 4th Avenue Suite 2500 Portland, Oregon 97204 503.545.3821 | |
| PROJECT NO. | 212024.02 |
| DRAWN | BJS |
| CHECKED | TCS |
| DATE | 04-15-2014 |
|  | |
| BID SET | |
| MARQUEE FRAMING PLAN | |
| S2.0 | |



1 MARQUEE SECTION
1" = 1'-0" S2.0



5 PIPE TO CHAIN
3" = 1'-0" S6.1

2 HSS BEAM TO CONC. WALL CONN.
1" = 1'-0" S6.1



6 STUD TO HSS
3" = 1'-0" S6.1

3 HSS BEAM TO HSS BEAM CONN.
3" = 1'-0" S6.1



7 HSS TUBE SPLICE
3" = 1'-0" S6.1

4 PIPE TO HSS BEAM
3" = 1'-0" S6.1

File: G:\A\2019\2024\02 Egyptian Theatre\2024020561.dwg TAB Layout1
Plotted: 4/21/14 at 11:44am By: thong
XREFs: x212024021B

| CITY OF COOS BAY | | | |
|---------------------------------------|------------|-----------|------|
| EGYPTIAN THEATRE PHASE 1 IMPROVEMENTS | | | |
| 229 SOUTH BROADWAY | | | |
| COOS BAY, OREGON | | | |
| PROJECT NO. | 212024.02 | BY | DATE |
| DRAWN: | BJS | REVISIONS | |
| CHECKED: | TCS | | |
| DATE: | 04-15-2014 | | |
| | | | |
| BID SET | | | |
| STRUCTURAL DETAILS | | | |
| S6.1 | | | |